



Everest Group of Construction UK Ltd

1 17 Stanley Park Road, Wallington, England, SM6 0HJ.
07494484706
Company number: 11069951

14/05/2023

Ratnam

9 Derek Avenue, KT19 9HP

Hi,

Re: First Floor Extension & Renovation Works

Please see below the quotation for the works to be done -

- Refurbishment of garage

As you are aware, we are discussing the conversion of a garage into a room. According to the blueprint, we must excavate it to a depth of 600 x 1000 mm before pouring concrete and building bricks. We must strengthen the roof with more timber before installing plaster board and insulation. They recommend installing 50mm insulating plasterboard on the side walls. We apply insulation and screed to the floor. In accordance with the plan, a door opening must be created in the existing wall. Build a bathroom with a shower, wash basin and toilet in the garage. As we discussed, the boiler has to be moved to the kitchen, the gas to the front and the electricity to beneath the stairs for safety reasons.

- First Floor Side Extension

According to the blueprint, we must remove the flat roof and construct a floor before putting up the 18mm plywood walls. Build two side external walls out of bricks and cement, then paint them. Installing 33mm thick insulated plasterboard with skim is required inside. Three beams must be installed for strength and form in accordance with construction regulations (in planning). This floor plan has one bathroom with a washbasin, shower and toilet.

We must open the door to the existing bathroom (noted in the plan) to enter the side expansion room. To do it, we must create a division. Existing windows that are used for bathroom access are closed, and new windows that are built are open at the back. There are also installed toilet, bath and washbasin. For the Roof we will do only as per the plan and building regulation.

- Bedroom 1

Removal of the current flat roof and construction the expansion has a continuation of the pitched roof. We will use wood, tails, fascia board and gutter to construct the roof.

- Electric Work and Plumbing work.

Each room 4 sockets and one light for new build. The existing wiring not changed but for main box do some extend wiring. For new build each room contain one radiator.

- Scaffolding

Is to be cover the whole house and roof

- Window and Door

4 window, 1 Fire exit door material and work (arranged by customer)

Please note that the following items to be supplied by customer -

Second fitting - Flooring, skirting board, Archi trey, (Door wall and Ceiling) paint, Door materials, Radiator, Boiler, Bathroom- tails, adhesive, grouts, toilet, wash basin, shower,

Please note the following: -

- Please note that Labor, all first fix building materials included.
- **Prices** are quoted only for the execution of the jobs listed with the necessary materials.
- Please make sure that the **planning permission** is in hand before the commencement of works.
- **Build period:** 12 weeks from date of commencement. The build period is specified in good faith and is subject to variations due to matters beyond our control, such as riots, strikes, lock outs, national calamities, and other acts of God.

Payment schedule.

Total price - £85200

Our quotation is based on the assumption that you shall make the following stage payments in realized funds/ cash to enable the smooth progress of the work.

[illegible]

Work program me – Once commenced our resources are programmed to continue the contract to completion unless compelled otherwise due to circumstances beyondour control “viz” default in payments, acts of God etc.

We trust we have quoted in line with your requirements and please add your signature to this document endorsing your agreement to this contract and we would be pleased to discuss concerns if any you have on this quotation.

Thanking you

Director

Customer

Anantha babu

Company number: 11069951